



Town of Redding

Department of Health

100 Hill Rd. Redding, CT 06896 (Town Hall)
P.O. Box 1028 Redding, CT 06875 (Mailing Address)

Phone: (203) 938-2559
health@townofreddingct.org

Criteria for Septic System Final As-Built

Address of Property: _____

Installer/Engineer: _____ Review Date _____

**Septic system final sketches must have all of the following data.
Unchecked items indicate information missing from the design drawing.**

- _____ Size of the final plan should be of a size **no less than (8 1/2" x 11")**
- _____ Address of property and Map, Block, Lot
- _____ Owner's name, address, and telephone number
- _____ Installer/Engineer name, address, phone number and license number
- _____ Sketch of property displaying accurate property lines (A-2 survey if possible)
- _____ Locate all existing and proposed structures including driveway, pool, tennis court, etc.
- _____ Plan should be to scale (1" = 20, 1" = 30)
- _____ Display North Arrow
- _____ Display side of house (front, rear); Shape of house must be accurately represented
- _____ Locate well(s) and/or water line(s)
- _____ Number of bedrooms _____
- _____ Location and size of old/existing septic tank/pump chamber
- _____ Locate wetlands & watercourses (if any)
- _____ Locate ground, surface, footing, and/or leader drains
- _____ Locate and define size of septic tank, pump chamber, soil line, force main, and all distribution lines
- _____ Locate limits of fill or mound systems and reserve areas if applicable.
- _____ Display table of ties for building served, tank, pump chamber, galleries/trenches, and d-boxes
- _____ Indicate whether the septic system is code compliant _____
- _____ Satisfactory Sieve Analysis of Select Fill _____
- _____ Date System was completed _____
- _____ Total square feet required _____
- _____ Total square feet of leaching area _____
- _____ Center to center distance between leaching units / 50-foot separating distance _____
- _____ MLSS required (show calculations) _____
- _____ MLSS provided _____
- _____ Total lineal feet of leaching area _____
- _____ Indicate the type of leaching system that was installed _____